

Project / Black Fold Apartments

Jan/Feb 2017

Location / 27-29 Bank Street, West End, Brisbane

Floor Count / 6



When the project manager says they will use Smart Hobs on all their jobs because they are 'so easy and strong', it's clear that the system is proving itself to be the preferred method for hob formwork construction.

hobs were installed and fixed into place by the wall and ceiling contractors. The hobs were then filled with concrete by the on site concreting team.

Black Fold is one of the latest projects making its entrance into the Brisbane market by Melbourne based developers, BPM Corp.

Installed as a permanent system, there is no need to wait for the concrete to set before stripping temporary ply and removing nails. Once the Smart Hobs are waterproofed, the construction teams are then able to immediately move to the next section or level.

The Smart Hob team worked closely with the developers, initially supplying 150 lengths to the specified size. Manufactured and then delivered to site, the

Hob Formwork: Easier, Smarter and Faster with SBS Smart Hobs.

